

**Project: Pier A Structural Repairs Project – Phase II  
General Contractor Services –  
Request for Proposals (“RFP”)**

**Date: August 15, 2023**

**Addendum #4  
# of Pages: 112**

---

**A) REVISIONS TO RFP:**

- 1) The following revised drawings are hereby formally incorporated into the RFP’s Exhibit B – Pier A Structural Repairs – Phase II Project Drawings and Specifications. These revised drawings replace and supersede all prior versions issued with the RFP.

***Drawing GN-2: General Notes Sheet – Attachment #1***

***Drawing S-1: Apron Piles and Pier Stems Repair Plan – Attachment #2a***

***Drawing S-9: Pile and Seel Repair Details – Attachment #2b***

- 2) As a reference point supporting the Project Scope of Work, an inspection report – appended hereto as Attachment #3 – dated November 30, 2020 that was prepared by Urban Engineers of New York, D.P.C. (the “2020 Inspection Report”) is hereby formally incorporated into the RFP as Exhibit J – Pier A Underwater Inspection for Phase 2 to 5 Supportive Maintenances.

**B) BPCA’S RESPONSE TO SUBSTANTIVE QUESTIONS:**

The following responses are provided to substantive questions received by Battery Park City Authority (“BPCA”) by 5:00 p.m. E.S.T. on August 7, 2023, in connection with this RFP. The Responses are provided in bold, italicized print immediately following the Questions. Please note that all capitalized terms shall have the same definitions as provided in the RFP.

1. Are we allowed to access under the pier to view the work?  
***Prospective Proposers are not permitted to access the area under the pier. Please refer to Exhibit J – Pier A Underwater Inspection for Phase 2 to 5 Supportive Maintenances for information regarding under-Pier conditions. The selected Proposer will be provided with pre-construction access to the Work area for inspection, and any minor updates to the Scope of Work determined to be required will be noted and verified at that time.***
2. Are any of the proposed construction activities for bid subject to or restricted by moratorium? If so, please clarify.  
***Yes; no in-water construction work will take place between November 1<sup>st</sup> and April 30<sup>th</sup>. Permits from the NYS Department of Environmental Conservation, the Army Corps of Engineers and the NYC Department of Small Business Services (“NYC SBS”) are required for in-water work.***
3. Is there access to the work area from land?  
***Yes, the Project Site will be accessible from land, and the selected Proposer will be provided access as needed. Note that construction fencing associated with the South Battery Park City Resiliency Project (“SBPCR Project”) will be installed at Pier A Plaza and other Pier A-related maintenance and construction work may be occurring concurrently. As a result, contractor coordination will be required.***
4. Can equipment and materials be staged on pier or upland? If so, please indicate where.  
***Any Project-related equipment and materials will need to be stored on the pedestrian promenade that surrounds the perimeter of Pier A, and not on Pier A Plaza. Coordination of equipment and material storage may need to be coordinated with other Pier A contractors.***
5. Is there opportunity to visit the site prior to bid, between Aug 2<sup>st</sup> [sic] and August 11<sup>th</sup>?

***Two (2) Project Site walk-throughs were held on July 24<sup>th</sup> and August 3<sup>rd</sup>, respectively. Prospective Proposers are welcome to visit the publicly accessible areas of the Project Site on their own as well.***

6. We respectfully request an extension to the RFI deadline.

***Please see Addendum #2 for an extension of the questions submission due date.***

7. Can a barge or barges be staged at Pier A for the duration of work, without need to shift locations due to other vessel activity or operations?

***See waterfront construction permit rules and regulations of the NYC SBS: <https://nyc-business.nyc.gov/nycbusiness/description/waterfront-construction-work-permits>. Note that the selected Proposer will not be allowed to tie off a barge at Pier A, and that the selected Proposer would be responsible for determining whether barge access in the surrounding waters is permissible.***

8. Are there photos, inspection reports, or condition surveys of the existing deficiencies available for review/reference?

***Please refer to the 2020 Inspection Report – which, as noted in Section A – REVISIONS TO RFP (above), is appended hereto as Exhibit J.***

9. Can we access underdeck prior to bid?

***See response to Question #1.***

10. What exactly is the cause or nature of the “previously failed repairs”?

***See response to Question #8.***

11. Due to the location and volume of repairs, we strongly recommend the use of shotcrete to perform the repairs listed below. Please confirm shotcrete is acceptable to perform the listed repair bid items, where conditions allow:

Item 4 Type 1 Spall Repairs

Item 5 Type 2 Spall Repairs

Item 8 Pier Stem Void Repairs

Item 9 Pier A Edge Void Repairs

Item 10 Replace Failed Concrete Repairs

Item 12 Breakwater Void Repairs

Item 13 Breakwater Spall Repairs

Item 14 Breakwater Undermining Repairs

***Following Contract execution, the selected Proposer may submit a Request for Information (RFI) regarding the use of any such alternate repair materials/methods.***

12. Please confirm all labor on the job is prevailing wage?

***Confirmed.***

13. Please clarify if the project is exempt of sales and use tax on permanent materials?

***For purposes of Sections 1115 and 1116 of the New York State Tax Law, BPCA qualifies as an exempt governmental entity.***

14. Please clarify if Steel Fascia Repairs are included in this bid. If so, please identify locations & provide dimensions. Drawings show a repair detail, however there does not appear to be a Bid Item pertaining to these repairs. Also, Scope of Services in Exhibit A does not indicate descaling or recoating of steel channel fascia.

***As noted in Section A – REVISIONS TO RFP (above), the relevant revised Drawings are appended as Attachments #1, #2a and #2b. Also, please refer to Specification Section 09 90 00 – Painting & Coating.***

15. Please clarify the Iron Girder Repair details on sheet S-9 correspond to bid Item 11 Girder Flange Repair. If so, please identify where on sheets S-4 through S-7 they are located and what the dimensions are.

***See the Legend item "Knife Edging of Girders" in Drawings S-4, S-5, S-6, and S-7.***

16. Are there any restrictions on work hours? Nights? Weekends?

***Night and weekend work is allowed with a BPCA permit. Note that some of the Work is also water tide-dependent, and the selected Proposer will need to consider that when devising its Work schedule.***

17. Is the Contractor responsible for any inspection(s)?

***No.***

18. Are we required to submit a letter from our surety with the proposal (bid), as indicated below?

***D. Payment and Performance Bonds:*** A payment bond and a performance bond will both be required for this Project. Please provide a letter from your surety(ies) stating that you are able to provide both such bonds, as required in the Standard Form of Contract (Exhibit D).

***Yes.***

---

*By signing the line below, I am acknowledging that all pages of this Addendum #4 have been received, reviewed and understood, and will be incorporated into the Proposal submitted. This document must be attached to the Proposal for consideration.*

---

Print Name (Above)

---

Signature (Above)

---

Date (Above)

Number of pages received:\_\_\_\_\_ <fill in>

*Distributed to: All prospective Proposers*

*[NO FURTHER TEXT ON THIS PAGE]*

**ATTACHMENT #1**  
**REVISED GENERAL NOTES DRAWING GN-2**

*(ATTACHED)*



1. SHIMS: CLEAR SELECT STRUCTURAL WHITE OAK HEARTWOOD, EDGE SAWN (I.E. GRAIN TO BE ROUGHLY PERPENDICULAR TO THE BEARING FACES OF THE SHIM), U.N.O.
2. OTHER TIMBER: SELECT STRUCTURAL MARINE GRADE SOUTHERN PINE THAT IS ROUGH CUT, U.N.O.
3. LEAD HOLES FOR LAG SCREW SHALL BE BORED AS FOLLOWS:
  - A. THE CLEARANCE HOLE FOR THE SHANK SHALL HAVE THE SAME DIAMETER AS THE SHANK, AND THE SAME DEPTH OF PENETRATION AS THE LENGTH OF UNTHREADED SHANK. THE DRILL BIT LENGTH SHALL BE  $\frac{1}{8}$ " LESS IN LENGTH AS IS REQUIRED TO ACCOMMODATE SHANK DEPTH.
  - B. THE LEAD HOLE FOR THE THREADED PORTION SHALL HAVE A DIAMETER EQUAL TO 70% OF THE SHANK DIAMETER.
  - C. THIS EQUIPMENT SHALL BE EXPOSED TO THE FIELD ENGINEER FOR REVIEW PRIOR TO DAILY USE.
4. THE THREADED PORTION OF THE LAG SCREW SHALL BE INSERTED IN ITS LEAD HOLE BY TURNING WITH A WRENCH OR BY ROTATING EQUIPMENT, NOT BY DRIVING WITH A HAMMER.
5. SOAP OR OTHER LUBRICANT SHALL BE USED ON THE LAG SCREWS OR IN THE LEAD HOLES TO FACILITATE INSERTION AND PREVENT DAMAGE TO THE LAG SCREW.

1. USE DENSO PRODUCT SEASHIELD SERIES 70, OR APPROVED EQUAL.
2. MATERIALS SHALL CONSIST OF DENSYL PETROLATUM COMPOUND, DENSO MARINE PILING PETROLATUM TAPE, DENSO GLASS OUTERWRAP 70, AND DENSO POLY-WRAP, OR APPROVED EQUALS.
3. INSTALL ALL PRODUCTS ACCORDING TO MANUFACTURER'S RECOMMENDED PROCEDURES.
4. REMOVE EXISTING PROTRUSIONS FROM PILES PRIOR TO INSTALLATION.
5. THOROUGHLY CLEAN ALL PILES PRIOR TO INSTALLATION. PILE MUST BE FREE FROM ALL NAILS, BOLTS, SPLINTERS, MARINE GROWTH, OR OTHER FOREIGN OBJECTS THAT COULD CAUSE DAMAGE TO MATERIALS.
6. PLUG AND FILL ALL HOLES AND SURFACE DEFECTS WITH DENSYL MASTIC PETROLATUM COMPOUND.
7. INSTALL IN SEQUENCE THE DENSO MARINE PILING PETROLATUM TAPE, DENSO GLASS OUTERWRAP 70, AND DENSO POLY-WRAP ACCORDING TO MANUFACTURER'S PROCEDURES.



1. A FLOATING TURBIDITY CURTAIN SHALL BE PLACED TO ENCOMPASS AREAS WHERE SEDIMENT MAY BE GENERATED AS A RESULT OF PROJECT WORK. A TURBIDITY CURTAIN MUST BE IN PLACE FOR ACTIVITIES THAT MAY GENERATE TURBIDITY, INCLUDING: PILE INSTALLATION OR EXTRACTION, PLACING CONCRETE UNDERWATER, DREDGING OR UNDERWATER DEBRIS REMOVAL, AND DEMOLITION.
2. THE CURTAIN HEIGHT SHALL NOT EXCEED 12 FT, AND SHALL BE SHORT ENOUGH TO MAINTAIN A 1 FT GAP BETWEEN ITS BOTTOM AND THE MUDLINE AT MEAN LOW WATER.
3. UNLESS NOTED OTHERWISE, THE TURBIDITY CURTAIN SHALL BE A TRITON TYPE III PERMEABLE SILT AND TURBIDITY BARRIER, OR APPROVED EQUIVALENT. WHERE NO TIDAL FLUCTUATION OR CURRENT EXISTS, A TYPE II BARRIER MAY BE USED. SUBMIT PROPOSED BARRIER SPECIFICATIONS, ALONG WITH THE MANUFACTURER'S RECOMMENDED CONDITIONS FOR USE.
4. 8"Ø EROSION CONTROL SEDIMENT LOGS SHALL BE PLACED ALONG THE WATER'S EDGE IN ALL AREAS WHERE SEDIMENT OR RUNOFF MAY ENTER THE WATER, THROUGHOUT THE DURATION OF THE PROJECT, TO PREVENT THE DISCHARGE OF SEDIMENTS INTO THE WATER.
5. ATTACH BUOYS WITH NAVIGATION LIGHTS WHERE REQUIRED BY THE COAST GUARD.

# ADDENDUM-3

**ATTACHMENT #2**  
**REVISED STRUCTURAL DRAWINGS**

*[NO FURTHER TEXT ON THIS PAGE]*

**ATTACHMENT #2A**  
**REVISED DRAWING S-1: APRON PILES  
AND PIER STEMS REPAIR PLAN**

*(ATTACHED)*



**ATTACHMENT #2B**  
**REVISED DRAWING S-9: PILE AND  
STEEL REPAIR DETAILS**

*(ATTACHED)*





**ATTACHMENT #3**  
**ADDED RFP EXHIBIT:**  
**EXHIBIT J: PIER A UNDERWATER INSPECTION FOR**  
**PHASE 2 TO 5 SUPPORTIVE MAINTENANCES**

*(ATTACHED)*



## **Pier A Underwater Inspection for Phase 2 to 5 Supportive Maintenances**

**For**

**Battery Park City Authority  
November 30, 2020**

**Prepared For:**

Battery Park City Authority  
200 Liberty Street, 24<sup>th</sup> Floor  
New York, NY 10281

**Prepared By:**

Urban Engineers  
of New York, D.P.C.  
One Penn Plaza, Suite 4125  
New York, NY 10119



## TABLE OF CONTENTS

<b>1</b>	<b>INTRODUCTION</b>
1.1	Purpose and Scope
1.2	General Description of Structure
1.3	METHOD OF INVESTIGATION
<b>2</b>	<b>2016 ROUTINE INSPECTION REPORT &amp; 2020 INSPECTION FINDINGS</b>
2.1	Pier A Rating and Recommendation
<b>3</b>	<b>SUMMARY OF EXISTING CONDITIONS RECOMMENDATIONS</b>
3.1	Timber Structure
3.2	Concrete Structure
3.3	Metal Structure Element
3.3.1	Iron Built-up Plate Girder
3.3.2	Fascia Built-up Channel
3.4	North Breakwater
Appendix A Location Map and Proposed Phases Plan by BPCA	
Appendix B Existing Drawings and Previous Inspection Documents from BPCA	
Appendix C	
Appendix C1 Pile & Pile Cap and Bracing	
Appendix C1-1 Photographs	
Appendix C2 Piers	
Appendix C2-1 Piers Photographs	
Appendix C3 Bulkhead Inspection	
Appendix C3-1 Bulkhead Photographs	
Appendix C4 Breakwater Inspection	
Appendix C4-1 Breakwater Inspection Photos	
Appendix D Top Side Inspection On Pier A Apron	
Appendix E Above Water Inspection	
Appendix E1 Relieving Platform Seawall Inspection Notes and Photos	
Appendix E2 Jack Arch Concrete under Deck Inspection	
Appendix E2-1 Jack Arch Concrete under Deck Inspection Photographs	

# **1 INTRODUCTION**

## **1.1 Purpose and Scope**

Battery Park City Authority (BPCA) engaged Urban Engineers of New York, D.P.C. (Urban) to inspect and provide a rehabilitation design of historic Pier A substructure. Urban teamed with Marine Infrastructure Engineering Solutions P.C. (MEIS) to assist with the underwater and above water investigation. The inspection focused on the underside of the deck; the apron piles; portions of the apron support elements; the northern breakwater; and above water defects as highlighted in the Phase 2 through Phase 5 recommended repair as found in the 2016 Pier A condition inspection report performed by McLaren Engineering Group.

In 2018-2019, BPCA completed the Phase 1 priority repairs that were recommended in the 2016 report. These repairs consisted of repairs to the Relieving Platform as well as repairs to the piers and underside of the deck between Piers 7 and 8, (Span 8). Other portions of Pier A were noted as being in satisfactory or fair conditions in the 2016 Routine Inspection Report and were recommended to be repaired on a phased basis. The report recommended the additional repairs to be complete in Phases 2-5. The current investigation evaluated these previous report findings, including existing defects and documented any changes or new defects to develop the design requirements for the Phase 2-5 maintenance repairs.

## **1.2 General Description of Structure**

Pier A was originally built in the late nineteenth century and served as the headquarters of the New York City Board of Dock Commissioners and Harbor Police. The pier was expanded at the end of the nineteenth century. Pier A continued to serve the city until 1992, when the pier was vacated and allowed to fall into disrepair. There were many inspections and evaluations of the pier house supporting structure throughout the end of the twentieth century and into the early twenty-first century.

In the original design, the inner timber column footing pads for the pier house were sitting directly on the jack arches and the outer concrete column footing strips were sitting on iron girders. After a 2010 intensive renovation, the original load distribution changed by upgrading the timber columns to steel columns and installing post-tension slabs to support the new column loads. The post-tension slabs run parallel to, and on top of, the iron girders and relieve the load on the existing concrete jack arches.

The northern breakwater is located on the southern inshore end of the pier and provides protection to the south-east corner of Pier A.

The pier apron is constructed of timber piles and framing and supports a concrete decking which provided a public walkway and restaurant seating area. Please see the attached drawing.

### **1.3 METHOD OF INVESTIGATION**

During October 2020, with the support of Urban's personnel, MEIS performed and above and underwater investigation and took detailed measurements of defective areas previously noted in the 2016 McLaren Routine Inspection Report.

The MEIS team was led by a registered Professional Engineer in the State of New York, with support from two additional engineers trained in underwater inspection. A diving support truck parked on the East apron deck while the divers assessed the underside of Pier A. Inspectors took measurements of concrete spalls and cracks under the jack arch concrete and deterioration of the iron beams that are exposed. They also visually inspected the underside of the apron deck timber structure, North breakwater wall surfaces, and bulkhead wall.

During two days in the third week of October, the team performed underwater inspections for the high priority areas of Phase 2. This was generally areas under the North, South, and West side of perimeter apron. They further inspected above water length of piles and under deck by boat at low tide. After review of tidal conditions, the crew resumed inspections for two days in the fourth week of October. These included above water investigation for Phases 3, 4 and 5, measuring the previous defects as indicated in the 2016 investigation report and recording any additional defects found.

## **2 2016 ROUTINE INSPECTION REPORT & 2020 INSPECTION FINDINGS**

Following the 2016 report repair recommendation by McLaren, the relieving platform and end span of under deck (span-8) were rehabilitated as part of the Phase 1 plan in 2018-2019. Therefore, those areas are not discussed in this report. These 2020 recommendations were guided by NYCEDC, Waterfront Facilities Maintenance Management System Inspection Guidelines manual.

### **2.1 Pier A Rating and Recommendation**

#### **Apron**

All of the perimeter piles along the Pier Apron were inspected. Interior piles were inspected if there were noted deficiencies in the 2016 report or if there were issues noted with adjacent perimeter piles. Based on findings, there are new recommendations to rehabilitate some advanced and severely damaged piles.

All timber pile caps were visually inspected and most of them are in satisfactory condition. A few locations show signs of splitting but they are likely due to excessive force during hardware installation and not affecting the main structure. All timber joists are in satisfactory condition except in one location, where the additional sister joist has split, however this has been rehabilitated in phase 1. The bottom of concrete deck metal formwork is still in good

condition, with no change from the 2016 findings.

### **Piers**

As per the 2016 priority inspection, the piers are satisfactory. Minor chamfer spalls were observed in three locations at Pier-2 and 4. Pier-3 and 7 had small openings, which appear to be original to the structure and are causing no stress or deterioration. The north-west corner of pier-7 was found to be in moderate condition, where there is undermining of the bottom of the concrete block foundation. It is believed that the concrete blocks are supported by piles, but these were not exposed. The 2016 report recommended to monitor this location and place sand bags around the south side of pier-7 for to deter future undermining at this location.

### **Iron Girders**

The bottom of iron girders are in poor condition, exhibiting advanced corrosion. The bottom flange rivets have 30% in section loss without bearing loss of rivet head. The web and top flange of the girders are covered by the concrete jack arches and were not inspected.

### **Concrete Jack Arches**

The concrete jack arches within Spans 1-7 are in poor condition and exhibit moderate cracking and moderate concrete spalling. The jack arches in Span 8 were repaired as part of the Phase I repairs.

### **Pier Fascia**

The pier deck perimeter concrete block is covered with a fascia that consists of a built-up channel-shaped iron section. This fascia is fixed on to the concrete block and that block is attached to the outer encasing girders (G1 & G6). Because of exposure to the weather, the outer fascia plates are corroded and the bottom of the concrete block is in fair condition, with moderate chamfer spalling.

### **Bulkhead**

Approximately 85% of the bulkhead structure is in satisfactory condition, the remaining 15% is classified as fair condition, where there are missing mortar joints, have already been repointed and 90%-100% of the mortar is intact. This will require monitoring during future routine inspection.

### **Northern Breakwater**

Overall, the northern breakwater structure is in fair condition. Medium and wide transverse cracks are developing on the side surface and on top of the walkway slab along the breakwater. Voids were found on the bottom of north breakwater near the mudline. The maximum size was approximately 1'-0" H x 3'-0" D.

The scope for our services only included the northern breakwater which is adjacent and parallel to the Pier A. Additional voids and crack lines were found compared to the 2016 inspection findings. We recommend that further inspection of the entire breakwater structure be considered so that any necessary design and construction could be completed simultaneously with the remainder of the pier. We anticipate one additional day of a diving would be

required to inspect the remaining area of the breakwater structure.

The following table provides a comparison of the condition ratings and repair recommendations of the 2016 and 2020 inspections.

Sr. No.	Structure	2016 Recommended Action		2020 Recommendation	
		Condition	Action Type	Condition	Action Type
	<b>Phase -2</b>				
I.	Pier A, Apron	Satisfactory	Routine	Satisfactory	Routine
	1) Fender Piles			Satisfactory	Routine
	2) Piles			Fair	Priority
II.	Pier A Main Structure				
	1) Piers	Satisfactory	Routine	Fair (Pier-7 NW corner undermining)	Priority
	2) Jack Arch Concrete, Span-7	Fair	Priority	Poor (more defects in outer bays)	Priority
	3) End Diaphragm Wall , Span-7	Fair	Priority	Poor (concrete spalling in all the bays)	Priority
III.	Pier A Iron Beam Bottom Flange, Span-7	Poor	Priority	Poor (developing corrosion, G1,G2, G5, G6)	Priority
IV.	Fascia Bay and Cladding, Span-7	Fair	Priority	Satisfactory	Priority
	1) Fascia Plate			Fair	Priority
	2) Concrete Fill			Poor (bottom chamfer spalling at south side)	Priority
V.	Bulkhead, Concrete Structure	Fair	Routine	Satisfactory (Repointing between the blocks with 90-100% mortar intact) (The void between masonry block and concrete foundation under north apron.	Routine
VI.	Breakwater, Concrete Structure	Fair	Routine	Poor (increasing no. of Voids and cracks)	Priority

		2016 Recommended Action		2020 Recommendation	
Sr. No.	Structure	Condition	Action Type	Condition	Action Type
	<b>Phase -3</b>				
I.	Pier A Main Structure				
	1) Jack Arch Concrete, Span-5 & 6	Fair	Priority	Poor (progressive cracking in span-6, bay 1 west)	Priority
	2) End Diaphragm Wall	Fair	Priority	Poor (concrete spalling in all the bays)	Priority
II.	Pier A Iron Beam Bottom Flange Span-5 & 6	Poor	Priority	Poor (more defects, concrete spalling in both span G2.	Priority
III.	Fascia Bay and Cladding, Span-5 & 6				
	1) Fascia Plate	Fair	Priority	Fair	Priority
	2) Concrete Fill			Poor (bottom chamfer spalling at both spans south side and span-6 north side)	Priority

		2016 Recommended Action		2020 Recommendation	
Sr. No.	Structure	Condition	Action Type	Condition	Action Type
	<b>Phase -4</b>				
I.	Pier A Concrete structure				
	1) Jack Arch Concrete, Span-3 & 4	Fair	Priority	Poor	Priority
	2) End Diaphragm Wall	Fair	Priority	Poor (new concrete spalling in middle bays)	Priority
II.	Pier A Iron Beam Bottom Flange Span-3 & 4	Poor	Priority	Poor (more concrete spalling in span-3, near bottom of the girders)	Priority
III.	Fascia Bay and Cladding, Span-3 & 4				
	1) Fascia Plate	Fair	Priority	Fair	Priority
	2) Concrete Fill			Fair (In span-4 bottom chamfer spalling are less than 2016 marked, span-3 are the same)	Priority

Sr. No.	Structure	2016 Recommended Action		2020 Recommendation	
		Condition	Action Type	Condition	Action Type
	<b>Phase -5</b>				
I.	Pier A Concrete structure				
	1) Jack Arch Concrete, Span-1 & 2	Fair	Priority	Poor (In span-2 new crack line found in East side of utility box and middle bay)	Priority
	2) End Diaphragm Wall	Fair	Priority	Poor (new concrete spalling on top of the Pier A in both span)	Priority
II.	Pier A Iron Beam Bottom Flange Span-1 & 2	Poor	Priority	Poor (more concrete spalling in both span G5 and G1&2 East corner)	Priority
III.	Fascia Bay and Cladding, Span-1 & 2				
	1) Fascia Plate	Fair	Priority	Fair	Priority
	2) Concrete Fill			Poor (bottom chamfer spalling at both spans south side and span-1 north side)	Priority



### 3 SUMMARY OF EXISTING CONDITIONS RECOMMENDATIONS

#### 3.1 Timber Structure

About half of the overall timber structure are in satisfactory condition. In the south pier apron, two piles exhibit moderate section loss which require priority repair action. Two fender piles are missing in west and north-west pier aprons. If these piles were purposefully removed at the time of renovation and reinforced with adjacent piles, there is no action required. All the timber pile caps and joists are in good condition however routine inspection is recommended. The Pier A south side has longitudinal and transverse bracing members installed between the piles. These members are in fair condition, with priority level repairs recommended near south fender rack. Please see appendix C1 for detail of defected member photographs.

This 2020 inspection relies on the previous inspection's recommended priority pile locations so not all of the piles were inspected. Marine borer damage was found on 30% of the piles that were inspected and will likely affect more in the years to come, therefore a long term schedule for repairs is recommended to prolong the life of these piles. There were no Marine borer damage noted in the piles in the 2016 routine inspection so it is recommended to check all piles at interior grid lines within the routine inspection period. Depending on those findings a decision should be made for the for the most effective and cost effective way to protect the piles.




Figure 1\_ Pier A Apron Timber structure



**Table 1 \_ Inspected Piles Condition**

Element	Number of Inspected Pile	General Condition				Remarks
		No. of Good Pile	Satisfactory Pile	Fair Pile	Poor Pile	
Fender Pile	60	-	40	20		
Apron Pile	93	-	65	26	2 (moderate section loss at Grid-18L & 23J)	-

### 3.2 Concrete Structure

The main stem of the granite block supporting the substructure piers are in approximately 85% satisfactory condition. The Top of the stems have end diaphragm walls from the jack arch concrete deck and the concrete spalling was found to be larger than the previous inspection. We recommend to provide patching with polymer concrete and maintenance to rejuvenate the full bearing area for the diaphragm walls which supports the transverse end of the arch deck. This repair will have a very tight schedule because of the clear working overhead space requirement and work progress is dependent on the elevation of the tide.

Each span has five bays of jack arch concrete deck. A total of thirty five bays of jack arch concrete are included in Phase 2 to 5. Each span has two exterior bays and three interior bays. The thickness of the deck at the crown of the arch is about 15 inches and does not contain reinforcement. and column footing pads are directly sitting on the deck. The consequence of this concentrated load and combined with an unreinforced deck appears to be over stressing and most of the longitudinal crack lines are found in the crown of arch concrete. When compared with 2016 report, there are two additional longitudinal cracks in span-4, where each additional longitudinal crack in span 2, 4 and 7. Transverse cracks were found in four of the bays. The locations are Span-1 Bay 1, Span-4 Bay 3 & 5 and Span-5 Bay 1. If compare with 2016 report, there were no transverse cracks in Span-2 Bay 4 & 5, Span-3 Bay 5. Our recommendation for the cracking line is to use polymer sealant concrete, which will prevent water infiltration from the crack lines and progressive spalling from adjacent concrete. Spalling of the Arch bottom of girder encasement concrete was found in many locations especially in outer girders, G1&6. Our recommendation for maintenance in this area is to remove the loose and weakened surface and then patch with polymer concrete and coat the surface. Please see appendix E2 for detail of defected area photographs.

### 3.3 Metal Structure Element

#### 3.3.1 Iron Built-up Plate Girder

The iron girders consists of built-up plate girders encased in concrete, which is part of the jack arch deck. The bottoms of iron girder flanges are exposed to the air and tidal water and are in poor condition. This corrosion has caused adjacent concrete spalls and cracks. The corresponding top girder flanges are encased in concrete and can not be inspected. The inner girders, G3 & G4 have additional plates on the bottom of the flange. Please see the below sketches extracted from 2008 deck evaluation report. Our recommendation for maintenance of the iron girder bottom flanges is to remove the corrosion and rusted surfaces with sandblasting and then painting with an appropriate marine coating. Please see appendix E2 for detail of defected area photographs - 85 to 90.




Figure 2\_ Inner Iron Girders section




Figure 3\_ Inner Iron Girders section

### 3.3.2 Fascia Built-up Channel

The paint on the pier perimeter fascia channel is peeling off, rusted and in fair condition. The channel is built-up with 3/8"x36" plates and two L3 1/2 x L3 1/2 x 1/2 " angles. They are connected to the adjacent concrete block with two rivets at equal spacing. This corrosion is purely ascetic and not a structural issue. The recommendation is to clean and repaint the surface.



**Figure 4\_ Inner Iron Girders section**

## 3.4 North Breakwater

The north breakwater structure has several cracks and voids, and is in fair condition. The elevation of the breakwater is the same as the deck and is connected between the south pier walkway. The walls are constructed with concrete and one layer of masonry block. These blocks are sitting on the concrete foundation which is supported by piles. This inspection references station 0+00 as the north east corner and measuring from right to left direction of seaside surface until end of west breakwater. There are four voids in the north breakwater and concrete joints exhibit spalling between blocks. Moderate undermining was found in between the breakwater bottom and concrete foundation at the mudline. The voids location are indicated in attached drawing. We recommend repairing all breakwater voids at the same time for cost-efficiency and implementing more protective action on the existing structure.

**REFERENCE DOCUMENTS:**

- 1) *PIER A DECK INSPECTION & EVALUATION REPORT, AUG 2008, PREPARED BY WEIDLINGER ASSOCIATES, INC FOR H3 HARDY COLLABORATION ARCHITECTURE LLC.*
- 2) *2009-2010 POST TENSIONED SLAB CONSTRUCTION PHOTOS*

**Appendix A   Location Map**

**&**

**Proposed Phases Plan by BPCA**





PIER-A LOCATION MAP






FILE NAME: P:\Proj\140\140950.12\10\_Dwg\CA00\3.0 Facility Plan.dwg PLOT TIME: Wed, 12 Oct 2016 - 9:00am LAST SAVE: Wed, 12 Oct 2016 - 8:52am BY: cweibler



HUDSON RIVER  
FLOOD  
EBB



- PHASE 1 REPAIRS ~ \$700,000
- PHASE 2 REPAIRS ~ \$680,000
- PHASE 3 REPAIRS ~ \$710,000
- PHASE 4 REPAIRS ~ \$710,000
- PHASE 5 REPAIRS ~ \$710,000

WARNING - IT IS A VIOLATION OF NEW YORK STATE EDUCATIONAL LAW, SECTION 7209.2, FOR ANY PERSON, UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR, TO ALTER THIS DOCUMENT IN ANY WAY. IF ALTERED, THE ALTERING PERSON SHALL COMPLY WITH THE REQUIREMENTS OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2

McLaren

ENGINEERING GROUP

applied ingenuity

131 W. 35th Street, 4th Floor, New York, NY 10001  
Tel: (212) 324-6300 Fax: (212) 324-6310  
www.mclaren.com

PROJECT

BATTERY PARK

NEW YORK, NEW YORK

SHEET TITLE

PIER PLAN

PROJECT NO.

140950.12

SCALE

AS NOTED

DATE

08/22/2016

DRAWN BY

CGW

CHECKED BY

BDB

DRAWING NO.

FIG 3

3 OF 14

SHTS

BY

REVISION


DATE

NO.

## **Appendix B Existing Drawings and Previous Inspection Documents from BPCA**



FILE NAME: P:\Proj\140\140950.12\10\_Dwgs\CADD\3.0\_Facility Plan.dwg PLOT TIME: Wed, 12 Oct 2016 - 9:00am LAST SAVE: Wed, 12 Oct 2016 - 8:52am BY: cwebber




**FACILITY PLAN**

16' 8' 0' 16'  
1/32" = 1'-0" FEET


WARNING - IT IS A VIOLATION OF NEW YORK STATE EDUCATIONAL LAW, SECTION 7209.2, FOR ANY PERSON, UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR, TO ALTER THIS DOCUMENT IN ANY WAY. IF ALTERED, THE ALTERING PERSON SHALL COMPLY WITH THE REQUIREMENTS OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2

<b>McLaren</b> ENGINEERING GROUP applied ingenuity		M. G. McLAREN, P.C. 131 W. 35th Street, New York, NY 10001 Tel: (212) 324-6300 Fax: (212) 324-6310 www.mgmlaren.com	
PROJECT		NEW YORK	
BATTERY PARK		NEW YORK	
SHEET TITLE		PIER PLAN	
PROJECT NO.		140950.12	
SCALE		AS NOTED	
DATE		08/22/2016	
DRAWN BY		CGW	
CHECKED BY		BDB	
DRAWING NO.		FIG 3	
		3 OF 14 SHTS	


FILE NAME: P:\Proj140\140950.12\10\_Dwgs\CADD\4.0\_Sections.dwg PLOT TIME: Wed, 12 Oct 2016 - 9:01am LAST SAVE: Wed, 14 Sep 2016 - 9:29am BY: ewabber



**A**  
**FIG 4** SECTION THRU PIER DECK (AT MID-SPAN)  
SCALE: 1/4" = 1'-0" FEET



**B**  
**FIG 4** SECTION THRU PIER DECK (AT PIER)  
SCALE: 1/8" = 1'-0" FEET  
NOTE:  
EXISTING BUILT-UP BEAM DETAILS FROM  
SIDNEY M. JOHNSON ASSOCIATES CONSULTING



**C**  
**FIG 4** SECTION  
SCALE: 1/8" = 1'-0" FEET

WARNING - IT IS A VIOLATION OF NEW YORK STATE EDUCATIONAL LAW, SECTION 7209.2, FOR ANY PERSON, UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR, TO ALTER THIS DOCUMENT IN ANY WAY. IF ALTERED, THE ALTERING PERSON SHALL COMPLY WITH THE REQUIREMENTS OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2

PROJECT NO. 140950.12		SCALE AS NOTED		DATE 08/22/2016		DRAWN BY CGW		CHECKED BY BDB		DRAWING NO.	
<b>FIG 4</b>											
4 OF 14 SHTS											


**McLaren**  
ENGINEERING GROUP  
applied ingenuity

M. G. McLAREN, P.C.  
131 W. 35th Street, 4th Floor, New York, NY 10001  
Tel. (212) 324-6300 Fax. (212) 324-6310  
www.mgmclaren.com

NO.	DATE	REVISION	BY

PROJECT  
**PIER A DIVE INSPECTION**  
NEW YORK, NEW YORK

SHEET TITLE  
**PIER A SECTIONS**



**PIER PART PLAN A**  
N.T.S.

- CRACK
- SPALL
- DELAMINATION
- KNIFE EDGING OF GIRDERS

PROJECT NO. 140950.12		SCALE AS NOTED		DATE 08/22/2016		DRAWN BY CGW		CHECKED BY BDB		DRAWING NO.	
PROJECT PIER A DIVE INSPECTION		NEW YORK		NEW YORK		NEW YORK		NEW YORK		NEW YORK	
SHEET TITLE PART PLAN A		FIG 6		6 OF 14		SHTS		COPYRIGHT © 2016, McLAREN ENGINEERING GROUP		Page 20 of 101	

**McLaren**  
ENGINEERING GROUP

131 W. 35th Street, 4th Floor, New York, NY 10001  
Tel: (212) 324-6300 Fax: (212) 324-6310  
www.mclareneng.com

**PROJECT**  
PIER A DIVE INSPECTION  
NEW YORK


**SHEET TITLE**  
PART PLAN A

**FIG 6**  
6 OF 14 SHTS

WARNING - IT IS A VIOLATION OF NEW YORK STATE EDUCATIONAL LAW, SECTION 7209.2, FOR ANY PERSON, UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR, TO ALTER THIS DOCUMENT IN ANY WAY. IF ALTERED, THE ALTERING PERSON SHALL COMPLY WITH THE REQUIREMENTS OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2

FILE NAME: P:\Proj140\140950.12\10\_Dwgs\CADD\6.0-8.0 Part Plans.dwg PLOT TIME: Wed, 12 Oct 2016 - 9:01am LAST SAVE: Wed, 14 Sep 2016 - 10:26am BY: cwebber

FILE NAME: P:\Proj140\140950.12\10\_Dwgs\CADD\6.0-8.0 Part Plans.dwg PLOT TIME: Wed, 12 Oct 2016 - 9:01am LAST SAVE: Wed, 14 Sep 2016 - 10:26am BY: cwebber



WARNING - IT IS A VIOLATION OF NEW YORK STATE EDUCATIONAL LAW, SECTION 7209.2, FOR ANY PERSON, UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR, TO ALTER THIS DOCUMENT IN ANY WAY. IF ALTERED, THE ALTERING PERSON SHALL COMPLY WITH THE REQUIREMENTS OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2

PROJECT NO. 140950.12	
SCALE AS NOTED	
DATE 08/22/2016	
DRAWN BY CGW	
CHECKED BY BDB	
DRAWING NO.	
BY	
REVISION	
DATE	
NO.	

**McLaren**  
ENGINEERING GROUP  
applied ingenuity

M. G. McLAREN, P.C.  
131 W. 35th Street, 4th Floor, New York, NY 10001  
Tel: (212) 324-6300 Fax: (212) 324-6310  
www.mgmclaren.com





**PROJECT**  
**PIER A DIVE INSPECTION**  
NEW YORK, NEW YORK

**SHEET TITLE**  
**PART PLAN B**

**FIG 7**  
7 OF 14 SHTS



N.T.S.

	CRACK
	SPALL
	DELAMINATION
	KNIFE EDGING OF GIRDERS

Page 22 of 101

COPYRIGHT © 2016, McLAREN ENGINEERING GROUP

[illegible]

**McLaren**  
ENGINEERING GROUP  
*applied ingenuity*



M. G. McLAREN, P.C.  
131 W. 35th Street, 4th Floor, New York, NY 10001  
Tel. (212) 324-6300 Fax. (212) 324-6310  
[www.ngmclaren.com](http://www.ngmclaren.com)

PROJECT

PIER A DIVE INSPECTION

NEW YORK, NEW YORK

SHEET TITLE

PART PLAN C

PROJECT NO.	140950.12
SCALE	AS NOTED
DATE	08/22/2016
DRAWN BY	CGW
CHECKED BY	BDB

FIG 8

OF 14 SHTS

**BATTERY PARK CITY AUTHORITY**

**PIER A & ADJACENT BULKHEAD,  
BREAKWATER AND LOW-LEVEL  
PLATFORMS  
ROUTINE CONDITION INSPECTION**

**NOVEMBER 2016**



**PIER A**

**DECK INSPECTION  
&  
EVALUATION REPORT**

**August 2008**

**Prepared by**

**Weidlinger Associates, Inc.**

**for**

**H3 Hardy Collaboration Architecture LLC**

## **Appendix C**

### **Under Water Inspection Area, Plan and Sections, Photographs & Notes**



## **Appendix C1 Pile & Pile Cap and Bracing**

# 1. Summary from inspected poor condition piles

No.	Grid No.	Description	Repaired requirement
1	(7 btw F&G)	Fender pile was missed in the location	Routine
2	7L	SW corner cluster - SE dolphin pile missing copper cap abrasion, splitting top 6"	Routine
3	9A	Fender Pile, Trace limnoria, Minor peeling in tidal zone 1/4"D.	Priority
4	9C	Pile Abrasion in tidal zone	Priority
5	11A	Mechanical gouge with trace of marine borer (limnoria), 6' above mudline NE side 2'H x 10"W x 1"D	Priority
6	17A	3/4"D Peeling in upper tidal zone	Routine
7	17B	Shallow shake in tidal zone	Routine
8	18L	Pile and brace connection was loose and lost.	Priority
9	23J	Active of marine borer (Torredo) on pile; visible section loss - 10% maximum; gauging on north side of pile, starts at 2 FT below water surface, 2.5 F H x 0.6 F W x 1.25 N D; Bottom comp - soft slope at base; probe of 4F+ into mudline. Ragworms photographed on pile surface next to calcified	Priority
10	23K	At 23, the bracing underneath the pier is no longer present east of 21; 21 is good; MN peeling intermittent on pile face, .25 N; localized deformity on pile at mid-pile;	Priority
11	27B	Likely old timber post	
12	27L	Minor peeling, trace of marine borer (Terredo); minor gauge 2.5' L x 4" W x 0.75" D on north face of pile	Priority
13	28	Pile section loss, Marine borer (Tredor) Water surface to mudline	Priority
14-34	Various	Tracing marine borer (Limnoria)	Priority
	<b>30</b>	<b>Total No. of priority repaired required pile</b>	

## 2. Summary from inspected pile caps and bracings

No.	Grid No.	Description	Future Inspection
1	8A	Bearing gap at the top of the pile, 50% bearing	Routine
2	12A	Damage to the bottom 30% of cap from North end to pile; repaired with sister boards were connected in place.	Routine
3	B (Btw. 8&9)	Check on east end of cap 1/2" max, 25' long	Good
4	19B	Full length crack in both sister boards on cap, 1/4" wide max;	Routine
5	30C	Partial bearing, east side 80-90%	Routine
6	19L	Loose diagonal brace Bent 21-22, disconnected at 21	Routine

## 3. South Apron Pier Fender Panel


No.	Grid No.	Description	Remarks
1	Btw 18 & 19	Ferry landing fender rack was serious condition and not allow to use ship berthing. Two marine fenders were missed and loose Buffer rails	Routine Inspection is required and Before structure repaired not allow to use for ship landing. Priority repaired, to fix the adjacent bracings



## **Appendix C1-1 Photographs**



**Photograph 1. Pile 10% section loss and Marine Borer found from water surface to mudline at Grid 23J**



**Photograph 2. Pile section loss and Marine Borer found from water surface to mudline at Grid 28**





**Photograph 3. Fender Pile was missed in Grid 7 between Grid F & G**



**Photograph 4. Pile Abrasion at Grid - 9C**





**Photograph 5. Pile peeling off at Grid - 17A**



**Photograph 6. Pile Shimming at Grid – 17B**



**Photograph 7. Pile Cap Bearing Loss at Grid - 8A**



**Photograph 8. Repaired Pile Cap with Corroded Bolts at Grid - 12A**





**Photograph 9. Repaired Pile Cap with Rusty Bolts at Grid – B (Between Grid 18 & 19)**



**Photograph 10. Pile Cap with Rusty Bolts at Grid – 19B**



**Photograph 11. Pile Cap Bearing Loss at Grid – 19B**



**Photograph 12. Timber Bracing connection loose at Grid – 19L**





**Photograph 13. Deteriorating Fender Panel and Lost Fenders**



**Photograph 14. Deteriorating Fender Support Bracings**

## **Appendix C2   Piers**



**Supporting Piers Field Notes**

No.	Grid No.	Description	Repaired Requirement
1	Pier-3	3 courses of masonry above the base of the concrete; Void in west face of pier 3 in course 2 located 5' north of the southwest corner 2 F H X 7 N W X 6 N D ; Looks like a deliberate cut-out, very uniform (photo); mortar mostly intact besides at low water between courses 2 and 3 - 60% missing; .75 N high by 6N deep VOD at horizontal joint between courses 2 and 3 over 60% of length. All other pointing 90% intact; missing mortar at horizontal joint between courses 2 and 3 on east face for full length of pier	Routine
2	Pier-6	Holes are present extending through the width of the pier, continuous on the pier face intended for construction. Photo taken at the south west corner (photo); piles on Bent 16 between FS and Pier 6 MN; Masonry MN; Pointing (mortar) intact; >10% missing; ND along west side; Fire protection system piping found between rows 16 and 17 south side of pier	Routine
3	Pier-7	Northwest corner Undermining: West Face = 1.4'L x 0.3'H x 2.0'D ML Comp is silt, sand, rock and debris. Northwest corner Undermining: North Face = 0.6'L x 0.2'H x 1.4'D Horiz. Penetration. Open hole thru pier at top of bottom course of concrete block, 1'W x 2'H with a curved taper from top to bottom to a horiz.. passageway 1'W x <1'H. There are 6 points (2 per block) across the length of the pier. 2 courses of concrete block at bottom with 3 courses masonry above. No additional passageways noted. Mortar mostly intact with 5-10% max missing mortar in lower tidal zone.	Priority

## **Appendix C2-1 Piers Photographs**



**Photograph 15. Pier-3 Mechanical cut on Pier Stem**



**Photograph 16. Pier-6 Open Cut on Pier Stem**





Photograph 17. Pier-7 North Face



Photograph 18. Pier-7 West Face



Photograph 19. Pier-7 Undermining NW Corner West Face (1.4'Lx0.3'Hx2.0'D)



Photograph 20. Pier-7 Undermining NW Corner North Face (0.6'Lx0.2'Hx1.4'D)



**Photograph 21. Pier-7 Horizontal Passageway (1'W x <1'H)**



## **Appendix C3 Bulkhead Inspection**

**Bulkhead Inspection Field Notes**

No.	Grid No.	Description	Repaired Requirement
1	35A	Masonry to ML, 7 courses exposed from top to ML. Mortar loss <10% below water near mudline, repairs visible in tidal zone extending above water 100% intact above water extending to visual limit to south (9:30 AM on 10/13/2020). Mortar intact full ht from bent 35 to north.	Routine
2		Mortar 100% intact above and below water from SE corner to north. Mortar joints typically 0.5" to 0.75" in height. Construction changes at northern pier fascia where pier meets north apron.	Routine
3		North Pier Fascia to Northern limit of inspection at bulkhead/riprap slope: Mortar joints vary in height from 0.05'H to 0.3'H. Blocks are uniform in size Course 5 = 1.9'H. Course 6 = 1.5'H. Course 7 = 2.0'H., mortar joints vary due to irregular edges. Broken blocks occur intermittently and are visible at MLW (bottom of 4th course from top). Vertical joints 0.3'W with failing mortar within. Horizontal joints get wider at 5th course extending down (below MLW). 7 courses exposed for height of wall. Vertical joints of courses 5-7 (alternating spacing ranges from 2' to 6'L, average =4') and horizontal joints 5/6 and 6/7. Joints have 25% mortar loss, 0.2' to 0.3' wide x 0.3' to 0.4' D (average measurements) for a length of 60'L extending from the north pier fascia. Isolated defect: Under pier bottom joint of course 7 = even with ML joint loss is 0.2'H x 1'D for 10'L under north apron. Isolated areas where penetrations in joints exceed 1'D.	Routine

## **Appendix C3-1 Bulkhead Photographs**



**Photograph 22. Bulkhead Joint Loss ~ 10 Ft (1'D x 0.2'H) under North Apron**



**Photograph 23. Bulkhead North End**





**Photograph 24. Bulkhead North**



**Photograph 25. Bulkhead Under the North Apron**



**Photograph 26. Bulkhead Adjacent to the North Apron**



**Photograph 27. Bulkhead North End**





**Photograph 28. Bulkhead North End**



**Photograph 29. Bulkhead North End**



**Photograph 30. Bulkhead North End**

## **Appendix C4 Breakwater Inspection**

### 1. Summary Voids and Joints Concrete Spall Location from Field Notes

No.	Grid No.	Station	Length (Ft)	Width (Ft)	Depth (Ft)	Repaired Requirement	Remark
<b>North Breakwater</b>							
1	Void	0+05	5	0.67	1.0	Priority	At Mud Line
2	Void	0+14	2	0.5	0.5	Priority	
3	Void	0+56.5	5	1.5	2	Priority	
4	Undermining	0+56.5	30	1.5	2	Priority	Open joint between one concrete block and the next below it; open spalled joint
<b>West Breakwater</b>							
5	Void	0+91	15	0.5	6	Priority	
6	Void	1+38	5	3	2.2	Priority	Large void at joint
7	Void	1+60	3	15	1.5	Priority	
8	Void	1+65	5	3	3.5	Priority	
9	Void	1+80	5	1.5	3	Priority	At vertical joint in bulkhead
10	Void	1+86	12	3	1.33	Priority	
11	Deterioration	0+91	8.5	1	1	Priority	

### 2. Summary of Crack Lines from Breakwater Side Surface

No.	Location	Number of Crack	Total Length (Ft)	Repaired Requirement	Remark
<b>North Breakwater</b>					
1	North surface	9	71	Priority	Max. crack width=1/4" Min. crack width=1/8"
2	South surface	21	115	Priority	Max. crack width=1/4" Min. crack width=1/32"

**Notes:** North Breakwater inspection is under Phase-2. West Breakwater and Memorial Breakwater are outside of Project Limit. Future inspection is required for repair work.







## **Appendix C4-1 Breakwater Inspection Photos**



Photograph 31. (30' L x 1.5' W x 2' D) Under Minding at Station 0+56.5, North Breakwater



Photograph 32. Void at the Base of Breakwater at Station 0+91, West Breakwater




Photograph 33. (15' L x 6" W x 6' D) Transverse Void under Water at Station 0+91, West Breakwater



**Photograph 34. Transverse Void above Water Level at Station 0+91, West Breakwater**





Photograph 35. (5'L x 3'W x 2.2'D) Void under water at Station 1+38, West Breakwater



Photograph 36. Breakwater wall concrete crack, South Surface, North Breakwater





**Photograph 37. Concrete crack lines on South Surface, North Breakwater**



**Photograph 38. Concrete crack lines on South Surface, North Breakwater**





**Photograph 39. Concrete crack lines on South Surface, North Breakwater**




**Photograph 40. Concrete crack lines on South Surface, North Breakwater**





Photograph 41. Concrete crack lines on North Surface, North Breakwater



Photograph 42. Concrete crack lines on North Surface, North Breakwater



Photograph 43. Voids between Blocks Wall on West Surface, West Breakwater





**Photograph 44. Tilted Blocks on West Surface, West Breakwater**



**Photograph 45. Concrete crack lines on East Surface, West Breakwater**





**Photograph 46. Fender Piles near West Breakwater (Routine inspection required)**



**Photograph 47. Voids between Blocks Wall on South West Surface, Memorial Breakwater**





**Photograph 48. Voids between Blocks Wall on South Surface, Memorial Breakwater**



**Photograph 49. Concrete Spalling at North East Corner, Memorial Breakwater**



**Photograph 50. Concrete crack lines on Walkway Slab every 5-10 ft, North Breakwater**



**Photograph 51. 0.6" Crack Width on Walkway Slab, North Breakwater**





**Photograph 52. Concrete crack lines on Walkway Slab every 5-10 ft, West Breakwater**

## **Appendix D Top Side Inspection**

### **On Pier-A Apron**



**Summary of Top Side Opening**

Mark-up ID	Area of Opening (Sq-Ft)	Description	Remarks
1	5	Opening in fender wall	
2	8	-	
3	4	4 Openings	
4	2	-	
5	1	-	
6	1	-	
7	20	Missing/ loose plank	
8	4	4 Openings	
9	1	At corner	
10	1	Likely old timber post	
11	-	Missing fender piles chocks missing	
12	1	-	
13	5	-	
14	2	2 Openings	
15	4	-	
16	4	4 Openings	
17	3	6 Openings	
18	2	3 Openings	
19	12	5 Openings	
20	4	Concrete spall on walkway pavement	Photo-2
21	2	2 Openings	
22	5	Loose plank.	
23	7	Loose and missing plank	
24	8	8 Openings	
25	11	11 Openings	
26	7	7 Openings	
	<b>120</b>	<b>Total area square feet of opening on plank</b>	






**Photograph 53. Top Side Openings in Pier-A North Apron**




**Photograph 54. Concrete spall on walkway pavement**



Photograph 55. Top Side Openings in Pier-A South Apron

## **Appendix E Above Water Inspection**









**Photograph 56. Pier-A South Elevation View**



**Photograph 57. Pier-A West Elevation View**



**Photograph 58. Pier-A North Elevation View (Landside)**



**Photograph 59. Pier-A North Elevation View (Seaside)**



## **Appendix E1 Relieving Platform Seawall**

### **Inspection Notes and Photos**

**Relieving Platform Seawall Above Water Inspection field Notes**

Mark-up ID	Area (Sq-Ft)	Description	Remarks
24	40	Missing granite blocks in upper courses.	Beside of project limit (Photo-5)
25	-	Missing mortar between courses 2-4; (3 horizontal + vertical) 50% 0.75" - 1.5" deep, 3" - 6" deep, 20 ft south of apron extending south	Project Area (Photo-1-4)
26	-	Missing granite block and spalled concrete core	Beside of project limit  (Marisol Sculptor Stone Label for American Merchant Mariners' Memorial, That stone behave as cantilever action and there has no reinforcements from concrete cap beam. Sonner or later adjacent granite stone wall and concrete cap beam will fall to the water.)  If that is under BPCA property immediately repaired are required for protection of adjacent seawall.  Photos – 6&7





**Photograph 60. Relieving Platform Seawall**



**Photograph 61. Relieving Platform Seawall under Ramp**





**Photograph 62. Relieving Platform Seawall between Ramp and Breakwater**



**Photograph 63. Relieving Platform Seawall Concrete Cap Beam**





**Photograph 64. Relieving Platform Seawall Outside of Project Limit**



**Photograph 65. Relieving Platform Seawall Outside of project limit**



Photograph 66. Seawall concrete cap displacement outside of project limit





Photograph 66. Seawall concrete cap displacement outside of project limit

## **Appendix E2 Jack Arch Concrete under Deck Inspection**


**Table 1. Summary of Defect under the deck**

Span No.	2020 Defect	Longitudinal Crack line at Crown of Arch Concrete Deck	Remarks
1	Number of Total defect 26, between Bulkhead and Pier-1	One crack line in middle bay (Bay-3)	(Bay-1) has less number of transverse crack lines than 2016 findings.
2	Number of Total defect 32, between Pier-1 and Pier-2	Two crack lines in (Bay-2) , (Bay-3) & (Bay-4)	No transverse crack lines in (Bay-4&5) from 2016 findings. Found three new longitudinal crack lines in 2020.
3	Number of Total defect 45, between Pier-2 and Pier-3	One crack line in middle bay (Bay-2)	No transverse crack lines in Bay-5 from 2016 findings.
4	Number of Total defect 23, between Pier-3 and Pier-4	Four crack lines in (Bay-2), (Bay-3), (Bay-4), (Bay-5)	Found one new longitudinal crack line in (Bay-3)
5	Number of Total defect 25, between Pier-4 and Pier-5	One crack lines in middle bay (Bay-3)	
6	Number of Total defect 33, between Pier-5 and Pier-6	Four crack lines in middle bay (Bay-1), (Bay-2), (Bay-3) & (Bay-4)	
7	Number of Total defect 33, between Pier-6 and Pier-7	Four crack lines in middle bay (Bay-2), (Bay-3), (Bay-4) & (Bay-5)	Found two new longitudinal crack lines in (Bay-2&3)

**Table 2. Comparison of longitudinal crack lines before and after post-tensioned slab renovated**

Span No.	2008 finding from Weidlinger Asso. (No. of Bay)	2020 findings (No. of Bay)	Remarks
1	0	1	+1
2	1	3	+2
3	2	1	-1
4	2	4	+2
5	1	1	0
6	3	4	+1
7	3	4	+1





**McLaren ENGINEERING GROUP**  
131 W. 20th Street, 4th Floor, New York, NY 10011  
Tel: (212) 334-4300 Fax: (212) 334-4310  
www.mclareneng.com


**PIER A DIVE INSPECTION**  
NEW YORK

**PART PLAN A**

**FIG 6**

PROJECT NO. 140950.12  
SCALE AS NOTED  
DATE 08/22/2016  
DRAWN BY CDM  
CHECKED BY RDB  
DATE





WARNING - IT IS A VIOLATION OF NEW YORK STATE EDUCATIONAL LAW, SECTION 7209.2, FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR, TO ALTER THIS DOCUMENT IN ANY WAY. IF ALTERED, THE ALTERING PERSON SHALL COMPLY WITH THE REQUIREMENTS OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2.

COPYRIGHT © 2016, McLAREN ENGINEERING GROUP

<p><b>McLaren</b> ENGINEERING GROUP</p> <p>130 W. 42nd St., 15th Floor, New York, NY 10018 Tel: 212-321-8444 Fax: 212-321-7422 www.mclareneng.com</p>	
<p><b>PROJECT:</b> PIER A DIVE INSPECTION</p> <p><b>LOCATION:</b> NEW YORK, NEW YORK</p>	
<p><b>SHEET TITLE:</b> PART PLAN B</p>	
<p><b>PROJECT NO.:</b> 140950.12</p> <p><b>SCALE:</b> AS NOTED</p> <p><b>DATE:</b> 08/22/2016</p> <p><b>DRAWN BY:</b> CCB</p> <p><b>CHECKED BY:</b> RCB</p>	<p><b>FIG 7</b></p> <p>3 OF 14 SHEETS</p>



## **Appendix E2-1 Jack Arch Concrete under Deck**

### **Inspection Photographs**





**Photograph 67. Span-1,#1, G6, Edge Beam Concrete Spalling**



**Photograph 68. Span-1,#11, Arch Transverse wall Concrete Spalling on Pier-1@Bay(5)**



**Photograph 69. Span-1,#17, G3 Bottom of the Iron Flange Efflorescence**





**Photograph 70. Span-1,#18, Concrete Spalling at Bay (2) on Pier-1**



**Photograph 71. Span-1,#21, Deteriorated Iron Beam & adjacent Concrete Spalling @ G2**





**Photograph 72. Span-1,#23, Deteriorated Tie Rod**



**Photograph 73. Span-1,#24, Arch concrete partially opening**



**Photograph 74. Span-3,#10, Concrete Cracking along the Iron Beam Bottom @ G5 Bay (5)**



**Photograph 75. Span-3,#19, Exposing Deteriorated reinforcement from Concrete arch**





**Photograph 76. Span-3,#28, Longitudinal Crack line at Bay (2)**



**Photograph 77. Span-4,#9, Longitudinal Crack line at Bay (4)**





**Photograph 78. Span-4, Concrete Cracks & Iron Beam Bottom flange Deterioration**



**Photograph 79. Span-6, #27 Concrete Spalling from Iron Beam Web (G2) and Deterioration**



**Photograph 80. Span-6, #10 Repaired Wooden Plug of Hole, expanded cracks surrounded**



**Photograph 81. Span-6, #30 Longitudinal Crack line at Bay (5)**





Photograph 82. Span-6, #9 \_ Arch Crown Crack width 4/16" in 10/22/2020 at Bay (4)



Photograph 83. Span-7, #2 \_ End Diaphragm Wall Bearing loss Pier-6 at Bay (4)





Photograph 84. Span-7, #11 \_ Arch Crown Longitudinal Crack at Bay (4)



Photograph 85. Span-7, View from G-1 , Pier-7



Photograph 86. Span-7, View from G1, Pier-6



Photograph 87. Span-6, View from G1, Pier-6





**Photograph 88. Span-5, View from G1, Pier-5**



**Photograph 89. Span-4, View from G1, Pier-3**





**Photograph 90. Span-3, View from G1, Pier-3**



**Photograph 91. Span-1, View from G1 to Bulkhead**